

WASTE WATER TREATMENT PLANT QIQIHAER

Heilongjiang Province - P. R. China



Schedule:

Contract in force: May 23, 2002

FAC: February 11, 2004

Capacity:

100.000m³/d

500.000 PE

Process Steps:

Coarse screen station, Influent lifting station, Fine screen station, Influent quantity and quality measurement, Longitudinal Grit and Grease removal, Primary Sedimentation, Aeration with submersible aerators, Blower Station, Final Sedimentation, Effluent quantity and quality measurement, Sludge Dewatering by gravity table and belt filter press, Sludge disposal by cake conveying system, Motor Control Center, PLC and Monitoring System

